ELSAFE INDIA

Leading The Way To Safey

Cochin - Chennai - Bangaluru - Hyderabad - UAE

www.elsafeindia.com, info@elsafeindia.com

CALL US AT 0484-2575199, 08848281812

CALL US AT 8848281812

Teksai | LSG PROTECT® | ALLTEC® SOLUTION PROVIDERS FOR AN ENERGIZED WORLD™

QUOTATION

Project Name: LSG TGD 30 | ELITE ESE PKG
Quote #: 56OQLSGP1
Company: Residential-Site
Total-Protection

These are Residential Packages for Houses at Kerala State only, ALL KERALA FREE DELIVERY, NO HIDDEN CHARGES

Revision:
Terms: ***
Ship via: Land Cargo
C&F: Landed at site
Weight: *** As applicable

LSG Protect-TGD 30 | ELITE	**Supply of External Lightning Protection System LSG PROTECT – Thunderguard® ESEs are made of non-corrosive materials, utilize advance and sustainable technologies, maintain a 15 Yrs warrenty, are independently tested certified to NFC 17102 and UNE 21186 standards. Level IV 75 mtrs by capturing dangerous lightning discharges and safely channelling it to earth. All mouting mast connected with FRP mast for Protection of Side Flash Lightning Current and Test link Joint Kit IP 55/65 weather proof enclosure for testing the earth pit.Insulation material used to electrically isolate the panels, The lightning air terminal is maintenance free type & frequent testing is not necessary for ensuring the working of it. The central finial shall be elevated above the spheroid and it is sharp pointed & made-up of stainless steel alloy for long and reliable operations. An air gap provided between the individual electrically isolated 4 panels and the finial tip of the central rod.**

Number	Item	Description	Qty.	Unit	Unit Cost	Total Cost
		Lightning Protection System			**(in INR)**	**(in INR)**
1	ThunderGuard TGD 30 | ELITE	LSG ThunderGuard TGD 30 | ELITE Lightning Arrester with SS ADAPTOR	1	No	INR 55,000	INR 55,000
2	Earthing	Maintenance free Earthing For Lightning Arrestor: Using 2 no's of 2 Mtr long / 250 micron, 16mm Dia DOLPHIN UL Listed Copper bonded Steel Rod & TEKSO ELECTRON Fill , a low resistivity ,RoHS certified & Maintenance free Grounding Enhancement backfill Compound Model:-TEKSO ELECTRON FILL(22 kg)	1	Set	INR 12,000	INR 12,000
3	Elevation Mast	Specially designed 3 mtrs GI mast Setting , and 1 mtr FRP top section insulation mast; Roof top/Tower side mounting arrangement & fixing accessories (anchoring rope & anchoring plate, Base -for roof top installation). The mast coated with paint for additional protection,Cable connector Adaptor	1	Set	INR 8,000	INR 8,000
4	Down Conductor	50 Sq MM **V Guard** HRFR Insulated Copper Cable with tester cables for ESE Lightnig Arrester tester	25	Mtrs	INR 1,100	INR 27,500
5	Conductor for SPD	10 sq mm VGUARD insulated copper cable	5	Mtrs	INR 200	INR 1,000
6	Surge Protector Device	LSG Protect BC100 | LSP FLP 320 Imported 3 Phase 1+2 Combicontrol 100KA AC Surge protection device	1	No	Complementory	Complementory
7	Fittings	COPPER LUGS, HDPE CLAMPS, BOLTS, SS SCREWS, FIXTURES, SEALENDS,waterproofing tapes, paint ETC	1	Set	INR 1,000	INR 1,000
8	Installation	**Installation of** ESE Lightning Protection System, tester system, SPDs with Down conductor routing from the LA terminal to the earth pit. Earth termination, fixing & Backfilling	1	Job	INR 10,000	INR 10,000
					SUB TOTAL	INR 1,14,500.00
					SEASONAL SPECIAL DISCOUNT	INR (20,000.00)
					GRAND TOTAL	INR 94,500.00

Terms & Conditions


1 GST 18% Extra | Transportation Extra at Actual, Ex Godown Cochin

2 Customers Scope: Material safety will be customer scope after delivery

3 Approvals /Permission of work/storage of tools & equipment/safety etc : At customers scope

Thank you,

Best Regards



ELSAFE PROTECTION & CONTROL SYSTEMS

CALL US AT 08848281812

6583 3254

Doc. No. : **ES252612121**

Rev. No. :

Rev. Date :

Sales and Service Provider of ALLTEC USA / LSG FRANCE/ TEKSAI-INDIA, Lightning Arresters, Surge Arresters, Maintanence free Earthing